

ADDENDUM NO. 1

June 3, 2009

Attention All Bidders and Plan Holders:

ARRA 2009 Project

Federal Aid Project No. ARRA-Y210(001) and ARRA-5667(003)

County Road Project No. 2140 and 2142

The following shall be replaced in the Contract:

APPENDIX – C and E

1) Contract Proposal and Plans:

Note Item 14 on the proposal and the contract summary of quantities includes class A signs. Class A signs will be provided, installed and maintained by the Contractor.

SPECIAL PROVISIONS

1). Replace **5-04.3(7) A Mix Design** with the following:

The maximum quantity of recycled material allowable in the hot mix asphalt for leveling and wearing courses shall be five (5) percent. The Contractor shall submit four samples of the designed mix to the Engineers representative for ignition furnace calibration at least five (5) days prior to paving. Samples shall be taken in conformance to WSDOT test method T 726.

All bidders will be required to furnish evidence of the receipt of this addendum on APPENDIX – C, Proposal – Signature Page. This addendum will be incorporated in and made a part of the contract when awarded, and when formally executed.

END OF ADDENDUM No. 1

Rod Lakey, P.E.
Assistant County Engineer