

CLARIFICATION

January 25, 2017

Attention All Bidders and Plan Holders:

Rebid Highway 603 Stabilization Project
Federal Aid Project No. STPR-G211(001)
F.A. Contract No. TA-5900
RAP Project No. 2108-01
CRP No. 2144

The following clarifications are:

Section 1-07.17

QWEST Field Engineering contact will be replaced by:

CenturyLink
Dena Overaa
Engineer II
South Bend, Raymond, Rochester,
Centralia, Chehalis, Napavine, Pe Ell
Curtis, Winlock, Vader
Office: (206) 733-5262
Cell: (425) 247-6248
Email: Dena Kludsikofsky@Centurylink.com

Added Utility contact:
City of Winlock – (360)785-3811
Utility Contact- Rodney Cecil (360)520-5589

Pipe:
Schedule A Culvert Pipe and Schedule A Storm Sewer Pipe from Stockpile:

Schedule A Culvert Pipe is”
18” x 20’ ADS F477 Pipe, AASHTO M294, Type “S” Non-Testable, 188500201B

Schedule A Storm Sewer Pipe is:
18” x 20’ ADS corrugated poly, Testable. AASHTO M294, Type “S”, 186500201B
24” X 20’ ADS corrugated poly pipe, AASHTO M294, Type “S” dual wall, 246500201B