

ATTENTION: All Bidders and Planholders

**Centralia Alpha Road MP 15.79
Culvert Replacement Project
CMP-1810
Addendum No. 1**

The Contract Special Provisions (Page 38) Section 2-02.3 *Construction Requirements* is supplemented with the following:

Wire Fence North of Centralia Alpha Road

The existing "New Zealand" style wire fence within the project limits (on the north side of Centralia Alpha Road) shall be removed and stockpiled while the Contractor completes all construction activities. Upon completion of all construction and planting mitigation, the Contractor shall reinstall the fence to its original condition using the existing wire and new fence posts of equal size/type. All costs for removing the existing fence, supplying new wood posts, and constructing the wire fence back to original condition shall be included and incidental to the lump sum price for "Removal of Structures and Obstructions".

Bidders shall furnish the County with evidence of receipt of this Addendum on the Proposal Signature Page for this Contract. This Addendum will be incorporated in the contract when awarded and when formally executed.



**Rod Lakey, P.E.
Project Engineer**

End Addendum No. 1